TUMKUR DIVISION.

Dated 12th November 1910.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to the 5th December 1910, for extending the English High School at Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the English High School at Tumkur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for extending the Government High School at Tumkur.

	Items of work.	*Per*	*Quantity.*
1.	Earthwork, excavation and filling basement	C. yd.	299
2.	Concrete	C. ft.	3,355
3.	Burnt stone in chunam	„	5,047
4.	Burnt brick in chunam	„	10,425
5.	Arch work, burnt brick in mortar	„	1,074
6.	Plastering with chunam	Sqr.	191·42
7.	Chunam pointing	„	7·00
8.	White and color-washing	„	214·72
9.	Burnt stone slabs, dressed	S. ft.	895
10.	Cuddapah slabs, 3" thick	C. ft.	182
11.	Flooring with Cuddapah slabs over 3" concrete and cement pointing	Sqr.	37·24
12.	Flooring with gravel	C. yd.	29
13.	Teakwood, wrought and put up	C. ft.	602·1
14.	Teakwood doors, complete (pannelled)	S. ft.	676
15.	Teakwood windows, inside glazed shutters outside pannelled	„	1,087
16.	Roofing with 1st class Mangalore tiles including teak reepers and chunam borders	Sqr.	64·77
17.	Terraced roofing	„	1·20
18.	Wood oiling	„	67·86
19.	Chocolate painting	„	19·66
20.	Ornamental ridge tiles set in mortar	R. ft.	199
21.	Cornice work	„	651
22.	Mouldings over windows and doors	„	233
23.	Teakwood planks, ¾" thick	S. ft.	40
24.	Zinc sheet for valleys	„	270
25.	Wire netting with teak frames	„	340
26.	Teakwood ornamental eave-boards	R. ft.	119
27.	Iron clamps	Each	200
28.	Teakwood finials	„	2
29.	Glass tiles	„	22
30.	Sun shades	„	18
31.	Tarring	Lump sum	
32.	Down pipes	Each	2
33.	Connecting old building with bond stones	Lump sum	
34.	Ornamental railings for porch	R. ft.	11
35.	Removing and refixing end windows	Lump sum	

K. ANANTACHARYA,
Executive Engineer.